

BILL OF QUANTITIES FOR AFFORESTATION- ANTI-EROSION WORKS - RASKA RIVER

CONDITIONS THAT MUST BE COMPLETED BY THE BIDDER

Seedlings for planting must be purchased in nurseries that can issue a certificate of planting material origin, as well as the declaration of the health status. During the transportation from the nursery to the planting place, seedlings must be kept safe from drying, and must be watered before they are offloaded.

After preparation of the ground, executing of the measuring for planting, manual digging of holes (with shovel, pick, pickaxe) at depth of 2m x 2,5m for spruce and 2,25m x 2,5m for acacia, the upper grass layer (layer of turf) has to be removed 0,5m from the centre of seedlings. Dimensions of the pit for planting are 30x30cm. Planting is carried out so that the seedlings are placed at the centre of the pit, and the neck of the seedlings is 1-2 cm below ground level (it is very important that the seedlings are evenly distributed in the pit, a bush-type layer of earth at the bottom of the pit grassy part downwards). After the completion of preparatory works, the fine grain soil should be put around the roots of seedlings and gently pressed in order to keep seedlings upright, and then gradually adding the rest of soil. On steep ground the mild embankment should be formed on the bottom side of the hole, so the moisture can be retained after rain. During the planting, seedlings roots should be protected from drying out. The quality and provision of quality assurance: the selected bidder is obliged to comply with the provisions of the Forest Act, the seedlings must have a Certificate of origin planting material, as well as the Declaration on the health status. The offered price should include transport of seedlings to the place of planting as well as making of all necessary access roads to the planned planting places.

Bill of Quantities for afforestation and grassing- Sebecevska River

	Description	Unit	Qty	Unit price RSD	Total
BIOLOGICAL WORKS					
1	Afforestation with spruce	ha	1.91		0.00
2	Grassing	ha	7.1		0.00
TOTAL					0.00

Bill of Quantities for afforestation and grassing- Dezevska river

	Description	Unit	Qty	Unit price RSD	Total
BIOLOGICAL WORKS					
1	Afforestation with acacia	ha	7.96		0.00
3	Grassing	ha	3.4		0.00
TOTAL					0.00

Bill of Quantities for afforestation and grassing- Ljudska river

	Description	Unit	Qty	Unit price RSD	Total
BIOLOGICAL WORKS					
1	Afforestation with spruce	ha	75.7		0.00
3	Grassing	ha	2.92		0.00
TOTAL					0.00

TOTAL SUMMARY

	Afforestation with spruce	ha	77.61		0.00
	Afforestation with acacia	ha	7.96		0.00
	Grassing	ha	13.42		0.00
TOTAL					0.00